UNDERGROUND INJECTION CONTROL PERMIT APPLICATION

Ute Tribal # 31-05 1980' FNL & 660' FWL Sec. 31, T5S-R3W Duchesne County, Utah API # 43-013-32035

July 2015

Prepared for:
Bruce Suchomel
Groundwater Program, Mail Code 8P-W-UIC
U.S. Environmental Protection Agency
1595 Wynkoop St
Denver, CO 80202-1129

Prepared by:
Petroglyph Energy, INC.

960 Broadway Avenue, Suite 500, P.O. Box 70019
Boise, Idaho 83707
(208) 685-7600
FAX (208) 685-7605

UNDERGROUND INJECTION CONTROL PERMIT APPLICATION

OCBL unrestable
amplified?

DEVIATION LOGS.

SUNDRY KPTS

CBIS FOR HOR WELLS

HOW WAS US DENDER INED

Ute Tribal # 31-05 1980' FNL & 660' FWL Sec. 31, T5S-R3W Duchesne County, Utah API # 43-013-32035

July 2015

Prepared for:
Bruce Suchomel
Groundwater Program, Mail Code 8P-W-UIC
U.S. Environmental Protection Agency
1595 Wynkoop St
Denver, CO 80202-1129

Prepared by:
Petroglyph Energy, INC.

960 Broadway Avenue, Suite 500, P.O. Box 70019
Boise, Idaho 83707
(208) 685-7600
FAX (208) 685-7605

LIST OF ATTACHMENTS

Attachment No. 1 Area Topography Map Attachment No. 2 Site Map Attachment No. 3 Map of the A-Marker surface Cross-Sections of the injection formation Attachment No. 4 Attachment No. 5 Water Analysis Completion data for all wells in the AOR Attachment No. 6 CBL for the UIC well Attachment No. 7 Open hole log for the UIC well Attachment No. 8 Attachment No. 9 List of owners and Affidavit Notification Well bore diagrams for the UIC well Attachment No. 10 Attachment No. 11 P&A procedure Attachment No. 12 MIT procedure

Surety Bond letter

Attachment No. 13

SUMMARY DOCUMENT UIC WELL APPLICATION Ute Tribal 31-05 API # 43-013-32035

The following document contains information provided in support of the application for the conversion of the Ute Tribal 31-05 well to an injection well in the Green River formation in the Antelope Creek Field in Duchesne County, Utah.

The Antelope Creek Field falls within the Uintah and Ouray Indian reservations and is within Indian Country; therefore, for facilities located on the reservation, only EPA-issued UIC permits are necessary for compliance with UIC regulations.

The EPA has issued an Area Permit #UT20736-00000 for the Underground Injection Control for the Antelope Creek Field. This area permit allows for additional producing wells to be converted to injection wells for enhanced recovery.

(1) Petroglyph Energy, Inc. (Petroglyph) is the operator and only working interest owner of wells located in the Antelope creek Field, Duchesne County, Utah. Petroglyph's business address is provided below:

Petroglyph Energy, Inc. 960 Broadway Avenue, Suite 500 P.O. Box 70019 Boise, ID 83707

- (2) Enclosed as Attachment No. 1 is a topographic map of a portion of the Antelope Creek Field, identifying all wells located in this area. The legal location for the Ute Tribal 31-05 is 1980' FNL & 660' FWL SW/NW Sec. 31, T5S-R3W.
- (3) Attachment No. 2 is a map of the well. This map shows a circle with a ¼ mile radius centered on the Ute Tribal 31-05 well. The ¼ mile radius encompasses the area of review, AOR, within which Petroglyph is required to investigate all wells for mechanical integrity. The ¼ mile radius also identifies mineral ownership; those lands, and the the owners thereof, which must be provided notice of this application. The AOR has Ute Tribal 31-04 and Ute Tribal 31-12 well(s) located in its ¼ mile radius.

- (4) Petroglyph proposes to utilize the Ute Tribal 31-05 as an injection well for enhanced recovery in the Antelope Creek Field.
- (5) Injection Zone The injection intervals are between 3420' and 5388' True Vertical Depth and located in the lower portion of the Green River Formation. The injection zone is confined within a 1968' section between the Green River "A" Lime marker bed and the top of the Basal Carbonate in the lower part of the formation. The injection zone is composed of lenticular calcareous sandstones interbedded with low permeable carbonates and calcareous shales. The lenticular sandstones vary in thickness from 1 to 30 feet.

Confining Zone – The overall confining strata above the injection zone consists of impermeable Green River calcareous shales and continuous beds of microcrystalline dolostone. The confining zone in the Ute Tribal 31-05 is 223 feet thick.

Attachment No. 3 is a structure map of the A-Marker surface.

Attachment No. 4 is a cross-section of the injection interval and confining zone.

- (6) Enclosed as Attachment No. 5 are standard analyses of produced water from three batteries that currently serve as central handling facilities for all project producing wells. The analysis of the Green River formation water from the Ute Tribal 18-08 Satellite Battery is 12805 mg/L of total dissolved solids (TDS), Ute Tribal 21-11 Satellite Battery is 15659 mg/L TDS, and Ute Tribal 34-12-D3 Satellite Battery is 14590 mg/L TDS.
 - Injectate in the field is a mixture of produced water and fresh make-up water. The nearest injection well is the Ute Tribal 19-13, the most recent analysis of the water being injected into the Green River formation at this location is 7342 mg/L TDS. This analysis is also included in Attachment No. 5.
- (7) A summary of completion data from the Ute Tribal 31-05 and offset wells in the AOR are included in Attachment No. 6
- (8) The cement bond log is included in Attachment No. 7.
- (9) The open hole log for the Ute Tribal 31-05 is included in Attachment No. 8.

- (10) The Antelope Creek Field is operated under a Cooperative Plan of Development between the Ute Tribe and Petroglyph Energy. At the Ute Tribal 31-05 location, all mineral owners, surface owners and operators located within the AOR ¼ mile radius have been notified of the submitted EPA application to convert to injection. Attachment No. 9 is the Affidavit of Notification to all owners.
- (11) Petroglyph requests a maximum surface injection pressure of **1730**psi. The EPA Area Permit No. UT20736-00000 uses the formula:

Pm = (0.88psi/ft - 0.43psi/ft(Sg)) D

Where:

Pm = Maximum surface injection pressure

0.88psi/ft = Fracture gradient

D = Top perforation depth

0.43psi/ft = Hydrostatic pressure/hydraulic head


Sg = Specific gravity of injection fluid


For the Ute Tribal 31-05:

1730psi = (0.88psi/ft - 0.43(1.00)) 3844ft


- (12) Three wellbore diagrams for the Ute Tribal 31-05 are in Attachment No. 10. One diagram is for production, one for injection, and one for Plug & Abandonment (P&A).
- (13) The P&A procedure for this well is shown in Attachment No. 11.
- (14) Once the draft permit is issued, Petroglyph will conduct a Mechanical Integrity Test and a static bottom-hole pressure test. The MIT procedure is contained in Attachment No. 12. The conversion work will be satisfactorily completed and submitted to the EPA on Form 7520-12. A wellbore schematic will be included with this form.


- (15) Petroglyph will give proof of financial responsibility by posting a surety bond for the UIC well prior to final permit approval. A copy of this letter is contained in Attachment No. 13.
- (16) Petroglyph will install various gauges on the well so that the injection pressure and tubing/casing annulus pressure can be monitored. The well will be equipped with a flow meter with a cumulative volume recorder.






ATTACHMENT NO. 2: SITE MAP






1:12000



ATTACHMENT NO. 3: Map of the "A" Lime Marker



Ute Tribal 31-05 Well History

Well History:

Spud Well: 3/14/1998 Completed: 4/30/1998 First Production: 5/6/1998

Tops (KB):

BMSW* Found at 1284'

Green River 954'

A Marker 3420'

X Marker 3895'

Douglas Creek 4034'

B Limestone 4400'

Castle Peak 4897'

Basal Carbonate 5388'

Perf History

4/25/1998

B11.1	3844' to 3848'
C02	3971' to 3975'
C06	4218' to 4221'
C09.2	4346' to 4352'
D01	4420' to 4424'
D3	4465' to 4468'
D3	4499' to 4502'
D7	4639' to 4643'
E01.1	4960' to 4966'
E01.2	5010' to 5016'

Petroglyph Operating Co., Inc.
Ute Tribal #31-05
(1980' FNL & 660' FWL)
SW NW Section 31, 5S-3W
Antelope Creek Field
Duchesne Co. Utah

API#: 43013320350000

GL: 6274'

KB: 6284'

8 5/8" 24# Surface CSG @ 368' KB

cmt'd w/300 sx

Surface Hole size 12 1/4"

Cement top @ 1656'

5 1/2" 15.5# J-55 CSG @ 5483'

-cmt'd w/430 sx

- Hole Size 7 7/8" bit

Perf's:

B11.1 3844' to 3848'

C02 3971' to 3975'

C06 4218' to 4221'

C09.2 4346' to 4352'

D01 4420' to 4424'

D3 4465' to 4468'

D3 4499' to 4502'

D7 4639' to 4643'

E01.1 4960' to 4966'


E01.2 5010' to 5016'

PBTD @ 5421' KB TD @ 5582' KB


(Not to Scale)

^{*}Plate 1 Utah Geological Survey Special Study 144. (2012). BMSW Elevation Contour Map, Uinta Basin, Utah. [map]. (CA 1:200,000)

Ute Tribal 31-05 Injection



Ute Tribal 31-05 Plug and Abandonment



Maximum Allowable Injection Pressure (MAIP) From Fracture Gradient

Date: 09/01/2015	Operator:	Petroglyph	
	Well:	Ute Tribal 31-05	•
	Permit #:		

Enter the following values:

Specific Gravity of injectate =
$$1.010$$
 g/cc

Depth to top of injection interval = $3,420$ feet

Fracture Gradient (FG) = 0.880 psi/ft

where:

MSIP = [FG - (0.433 * SG)] * Depth to top of injection interval = 1513.931

Cement Bond Index (in millivolts - mV)

Date: September 1, 2015

Operator:

Petroglyph

Well:

Ute Tribal 31-05

Permit:

Enter the following values:

$$(in \ mV) = 72 \quad m$$

Amplitude at 100% Bond (A-100) (in
$$mV$$
) =

Amplitude at 80% Bond (A-80) = 4.1 _{mV}

 $[(0.2)\log A0 + (0.8)\log A100]$

$$[(0.3)\log A0 + (0.7)\log A100]$$

$$[(0.4)\log A0 + (0.6)\log A100]$$



- Technical Review Worksheet

Permit No: <u>UT2</u>

. Well: <u>UT 31-05</u>

What Needs to be Done	Information Sources	Review & Evaluation Notes
Determine name, top and base of the confining zone(s) and the injection zone(s).	☐ Geologic data submitted☐ Well logs from area☐ Published articles	Conf Zone: top 3201 base 3420 Inj Zone: top 3420 base 5388 (Garden Gulch 2-Marker) (top Wassatch)
Determine name, top and base of all USDWs. List base of lowermost USDW: Determine which USDWs are actually being used for water supply.	☐ Geologic data submitted ☐ hearby Water analyses ☐ nearby Well logs ☐ Water supply wells ☐ Published articles	Surface Elevation: GL 6274 KB 6284 Pub #92 base USDW: bgs: elev: submitted base USDW bgs: 1284 elev: base of Uinta / top Green River: 954 GREENA
Review and evaluate construction, casing and cementing records of proposed well. Review and evaluate construction, casing and cementing records of AOR wells that penetrate injection zone.	Data submitted Completion/workover reports Contractor invoices Logs: CBL, RTS, Temp, casing inspection, etc.	TD: 5582 PBTD: $542/$ surface csg 8% 24# ft 0-368 long strg csg 5% 15.5# ft 0-5483 TOC: submitted: 16861365 CBL: $/565$ Wells in AOR: TD TOC $31-12$ 5452 1780 $36-08E$ $31-04$ 5517 170 $31-06$ $31-07$ deviste
Review P&A plan for effective USDW protection, injection zone	☐ P&A plan ☐ Area geology	plug depths:
Review amount of FR - is it adequate to cover P&A costs of proposed in P&A plan?	☐ contractor bids / P&A cost histories ☐ nearby well P&A costs	FR instrument: Amount: \$
Calculate the maximum allowable injection pressure (MAIP).	□ Fracture treatments □ Step Rate Test results □ Fracture gradient	top perforation: 3844. bottom perforation: 5028 injectate specific gravity: 1.01 Frac Gradient: .88 initial MAIP =
Determine which logs and tests will be performed.		